HANDLING INSTRUCTIONS






INSTALLATIONS SEQUENCE

- Lateral space excavation between 200 - 500 mm from the tank
- Stable area at least 2 m from the excavation.
- Installation of a concrete slab at the bottom of the excavation.
- Add a 50 mm sand bed to level the tank




- Handle the tank with straps and appropriate equipment.
- Make the necessary electrical and hydraulic connections.

- Add 1/3 of water to the tank
- Add 1/3 of stabilised sand of backfilling.
- · Watering the backfilling.



- Continue the procedure for 2/3 and 3/3 of the tank height.
- Don't forget to water the back filling at each layer.



- Final backfill the tank with up to 300 mm of vegetal soil.
- Keep covers accessible at all


'ENTION



NEVER fill the tank completely without accompanying it with the



NEVER carry out the backfill of the tank with the tank empty.




MUST NOT be higher than 1/3 of the height of the tank. It is necessary to anchor the tank to the slab with straps

If the water table is higher than 1/3, please contact us

GENERAL CONDITIONS

GENERAL CONDITIONS

Excavation bed



Lateral backfilling Stabilised sand - 100 kg oper m³ of sand (3-6 mm). Backfilling well compacted. Width >200 mm. If the soil is clayey or difficult, the proportion is 200 kg of cement per m³ of sand

Concrete slab

Slab dimensioning must be validated by a competent technician.

DEEP CONSTRUCTION (>30 CM), OR TRAFFIC AREAS

Support slab for load distribution

Executed in such a way that no load is transmitted to the equipment. Supported > 500 mm on each side of the excavation.

Lateral backfilling

Stabilised sand - 200 kg of dry cement per m³ of sand (3-6 mm). Backfill well compacted. Width >200 mm

Straps

Use anchoring straps made of fabric (not metallic).

Concrete slab

Slab dimensioning must be validated by a competent technician.

Excavation bed

50 mm of compacted sand of 3-6 mm.

At the end of the product's life, return it to an authorised waste manager.



