

Prüfinstitut für Abwassertechnik GmbH

*Prüfeinrichtung des Prüf- und Entwicklungsinstituts  
für Abwassertechnik an der RWTH Aachen*



DIN EN ISO 9001:2000

# **Report on the treatment efficiency test according to EN 12566-3 of the**

**ASP 06**

**of**

**Premier Tech Ltd.**

**Test report - No. PIA2008-086B25.02**

Aachen, February 2009 – rebranded in April 2015

A handwritten signature in blue ink, appearing to read "Elmar Lancé".

Dipl.-Ing. Elmar Lancé

**PIA GmbH**  
Prüfinstitut für Abwassertechnik  
Hergenrather Weg  
52074 Aachen



## TABLE OF CONTENTS

<b>1</b>	<b>INTRODUCTION .....</b>	<b>3</b>
<b>2</b>	<b>DESCRIPTION OF THE SMALL WASTEWATER TREATMENT PLANT ASP 06.....</b>	<b>4</b>
2.1	DESCRIPTION OF THE TANK.....	5
2.2	DESCRIPTION OF THE TREATMENT PROCESS.....	10
2.3	WATERTIGHTNESS TEST.....	10
<b>3</b>	<b>SAMPLING AND ANALYTICS.....</b>	<b>11</b>
<b>4</b>	<b>COURSE AND PARTICULARITIES OF THE EXAMINATION .....</b>	<b>12</b>
<b>5</b>	<b>TREATMENT EFFICIENCY .....</b>	<b>15</b>
5.1	INDIVIDUAL RESULTS .....	15
5.2	EVALUATION OF THE TEST SEQUENCES .....	22
5.3	GRAPHICAL PRESENTATION .....	25
<b>6</b>	<b>ASSESSMENT OF THE GENERAL PLANT SAFETY .....</b>	<b>32</b>
6.1	OPERATIONAL SAFETY OF SYSTEM COMPONENTS.....	32
6.2	SLUDGE REMOVAL .....	32
6.3	MAINTENANCE AND SELF-CHECKING.....	32
6.4	ACCESSIBILITY.....	32
<b>7</b>	<b>ANNEX.....</b>	<b>33</b>

## 1 Introduction

Due to a company takeover of the original owner Conder Solutions Ltd. of the test report PIA2008-086B25 this report was issued for the use by the company:

Premier Tech Ltd.  
2 Whitehouse Way  
South West Industrial Estate  
Peterlee  
Co Durham, SR8 2RA  
United Kingdom.

PIA GmbH  
Hergenrather Weg 30  
52074 Aachen  
Germany

received an order for a practical examination of the treatment efficiency of a ASP 06 – small wastewater treatment system according to EN 12566 Part 3 Annex B. The system was charged with a hydraulic daily flow of 1.2 m<sup>3</sup>/d domestic wastewater.

The examination started subsequent to the biomass establishment, on 22.10.2007 and ended on 13.07.2008.

The PIA GmbH has a certified quality management system according to DIN EN ISO 9001:2000 for the field "testing of wastewater equipment" and is approved by the European Commission as a testing authority "Notified Body" (NB 1739) according to the Construction Products Directive (CPD) for small wastewater treatment systems for up to 50 PE according to EN 12566-1 and EN 12566-3.

*The test results contained in this report refer solely to the tested objects. This report may only be reproduced – completely or in parts – if written consent has been given by PIA GmbH.*



## 2 Description of the small wastewater treatment plant ASP 06

The small sewage treatment plant ASP 06 is part of a range of systems. Due to the requirements of the EN 12566 part 3 the ASP 06 as the smallest model of the range, was tested by the PIA GmbH.



Figure 1: The ASP 06 with a non-original cover installed on the testing field of the PIA GmbH

## 2.1 Description of the tank

The small sewage treatment plant ASP 06 by Premier Tech Ltd. is a GRP tank consisting of a biological aeration zone in the centre and an outer settlement zone. The access cover is made of zinc coating steel and is fixable by screws. A control box with a blower is situated next to the treatment plant.

The dimensions of the tank were checked by the PIA and were found in accordance with the specifications given by the manufacturer.



Figure 2: The ASP 06



Figure 3: View into the empty ASP 06



Figure 4: View into the operating ASP 06



Figure 5: Original cover of the ASP 06





Figure 6: Blower of the ASP 06 with a capacity of 100 l/min.

## 2.2 Description of the treatment process

In the bioreactor of the small wastewater treatment plant ASP 06 by Premier Tech Ltd. the wastewater is treated with an aerated biological process.

The wastewater enters the biological zone directly. There it is treated by aerobic bacteria. An upright tube with a bubble diffuser in it creates a vertical circular drift within the cone-shaped zone (compare drawing on page 37). At the bottom of the cone tip the wastewater can emerge into the outer settlement chamber. After clarification in the outer zone, the treated water leaves the treatment plant by gravity flow.

A detailed description of the system (manufacturer's information) can be found in the annex of this report.

## 2.3 Watertightness test

The test for watertightness of the tank was carried out on 10<sup>th</sup> of September 2007. The test procedure complied with the EN 12566-3 Annex A.2 "Water test". Due to inaccurate lamination of the tank there was a detectable leakage.

A second test for watertightness with a new tank was executed on the 19<sup>th</sup> of September 2007. The tank was watertight and the plant ASP 06 therefore passed the watertightness test.



### 3 Sampling and analytics

For the test of the treatment efficiency of the ASP 06 small sewage treatment system according to the EN 12566-3 Annex B, all influent and effluent samples were taken as flow-based 24-h composite samples. The bioreactor was sampled by grab samples.

The following parameters were analysed:

Inflow : Temp., pH, COD, BOD<sub>5</sub>, NH<sub>4</sub>-N, N<sub>tot</sub>, P<sub>tot</sub>, conductivity, suspended solids (SS), settleable solids, turbidity

Bioreactor : Temp., SSV<sub>30</sub>, MLSS, O<sub>2</sub>

Outlet : COD, COD<sub>fil</sub>\*, BOD<sub>5</sub>, NH<sub>4</sub>-N, NO<sub>3</sub>-N, NO<sub>2</sub>-N, N<sub>tot</sub>, P<sub>tot</sub>, pH, conductivity, suspended solids (SS), settleable solids, turbidity

The parameters COD, BOD<sub>5</sub>, NH<sub>4</sub>-N, NO<sub>3</sub>-N, NO<sub>2</sub>-N, N<sub>tot</sub>, P<sub>tot</sub>, SS and MLSS were analysed by IWA "Institut für Wasser- und Abwasseranalytik", Jülicher Str. 336 in 52076 Aachen. IWA uses the standard analytical methods that are required by the EN 12566-3 annex B. IWA is accredited according to DIN EN ISO/IEC 17025:2000-04 and is part of the PIA accreditation as a notified body.

---

\* COD filtrated



## 4 Course and particularities of the examination

Due to the requirements of the EN 12566 part 3, the dosing of the tested treatment plant is divided into periods of nominal loading (100%), underloading (approximately 50% of the nominal loading in sequence 2 and 8) and overloading (150% of the nominal loading for 48 hours at the beginning of sequence 6). The progression of those scenarios throughout the whole testing period is shown in Table 1.

The power breakdown in test sequence 3 and 7 stands for a 24-h power cut-off two weeks after the start of the respective sequence. Low occupation stress / vacations means, that during the whole scenario no influent is dosed into the plant.

This testing report No PIA2008-086B25.02 is a revised version of the testing report No PIA2008-086B25. The company name was changed to Premier Tech Ltd.

Table 1: Test schedule

Sequence	Characteristics	Duration / Date
	Start of test	22.10.2007
1	Nominal	6 weeks
2	Underloading	2 weeks
3	Nominal / Power Breakdown	6 weeks
4	Low occupation stress / vacations	2 weeks
5	Nominal	6 weeks
6	Overloading	2 weeks
7	Nominal / Power Breakdown	6 weeks
8	Underloading	2 weeks
9	Nominal	6 weeks
	End of test	13.07.2008

During the nominal loading phases the system was charged with 1.2 m<sup>3</sup>/d wastewater and a nominal organic load of 0.37 kg/d.



This testing report No PIA2008-086B25.02 is a rebranded version of the testing report No PIA2008-086B25. Due to a company takeover of the original owner Conder Solutions Ltd. this report was issued with the new company name Premier Tech Ltd..



The charging of the small sewage treatment plant was carried out according to the daily flow patterns taken from the EN 12566-3 shown in Table 2.

Table 2: Daily flow patterns

Time	Percentage of daily volume [%]
3	30
3	15
6	0
2	40
3	15
7	0

During the entire test period an average power consumption of 2.6 kWh/d was determined.



## 5 Treatment efficiency

Section 5.1 deals with the individual results of all 26 influent and effluent samples.

The evaluation of the results in terms of mean, minimum and maximum values as well as the appropriate standard deviations of the tested system can be found within section 5.2 in Tables 9 to 12.

To display the treatment efficiency and the concentrations of the influent and effluent of the tested system more clearly, the results of all test sequences are graphically shown in section 5.3.

### 5.1 Individual results

The individual results of all parameters are listed in Tables 3 to 8.



Table 3: Results from 31.10.2007 to 06.12.2007

Test schedule		1	1	1	1	2
		100 %	100 %	100 %	100 %	50 %
Date		31.10.2007	08.11.2007	15.11.2007	22.11.2007	06.12.2007
Air Temperature min/max	[°C]	2/10	4/9	0/5	3/11	5/12
<b>Influent:</b>						
Temperature	[°C]	10.2	11.7	7.9	9.8	11.2
COD	[mg/l]	449	830	697	928	635
BOD <sub>5</sub>	[mg/l]	201	271	242	393	371
NH <sub>4</sub> -N	[mg/l]	22.0	28.6	28.0	32.6	21.2
N <sub>tot</sub>	[mg/l]	41	54	39	63	48
P <sub>tot</sub>	[mg/l]	6.4	7.9	7.8	11.4	7.9
pH	[ $\cdot$ ]	7.2	7.3	7.1	7.0	7.0
Conductivity	[ $\mu\text{S}/\text{cm}$ ]	646	805	679	832	746
SS	[mg/l]	308	328	450	620	436
Settleable solids <sub>120</sub>	[ml/l]	15	16	30	40	30
Turbidity	[FNU]	150	152	174	210	189
Faecal coliforms	[1/100ml]	-	-	-	-	-
<b>Effluent:</b>						
COD <sub>hom</sub>	[mg/l]	38	53	42	44	40
COD <sub>fil</sub>	[mg/l]	24	21	35	38	15
BOD <sub>5</sub>	[mg/l]	6	13	7	8	9
NH <sub>4</sub> -N	[mg/l]	1.7	4.7	4.6	10.4	1.6
NO <sub>3</sub> -N	[mg/l]	20.4	18.2	11.9	17.5	22.6
NO <sub>2</sub> -N	[mg/l]	1.6	2.5	1.2	1.2	0.4
N <sub>inorg</sub>	[mg/l]	23.7	25.4	17.7	29.1	24.6
N <sub>tot</sub>	[mg/l]	25.0	30.0	17.7	31.4	25.7
P <sub>tot</sub>	[mg/l]	3.6	3.8	2.5	3.8	3.1
pH	[ $\cdot$ ]	6.9	7.0	7.4	7.0	6.8
Conductivity	[ $\mu\text{S}/\text{cm}$ ]	579	629	535	689	550
SS	[mg/l]	13	22	11	4	14
Settleable solids <sub>120</sub>	[ml/l]	< 0.1	0.1	< 0.1	0.7	0.7
Turbidity	[FNU]	3.8	11.2	4.0	4.7	7.5
Faecal coliforms	[1/100ml]	-	-	-	-	-
<b>Biology:</b>						
Temperature	[°C]	11.9	11.9	8.9	10.5	10.1
SSV <sub>30</sub>	[mM]	400	100	100	170	240
MLSS	[g/l]	1.5	1.1	0.8	1.6	2.3
O <sub>2</sub>	[mg/l]	3.0	4.7	7.2	3.0	5.2



Table 4: Results from 13.12.2007 to 17.01.2008

Test schedule		2	3	3	3	3
		50 %	100 %	100 %	100 % *PB	100 %
Date		13.12.2007	20.12.2007	28.12.2007	10.01.2008	17.01.2008
Air Temperature min/max	[°C]	1/5	-5/4	-6/4	0/8	2/3
<b>Influent:</b>						
Temperature	[°C]	10.0	9.2	9.2	9.1	9.1
COD	[mg/l]	547	736	995	952	488
BOD <sub>5</sub>	[mg/l]	201	377	476	419	201
NH <sub>4</sub> -N	[mg/l]	23.8	50.6	32.0	33.2	32.6
N <sub>tot</sub>	[mg/l]	40	83	59	50	46
P <sub>tot</sub>	[mg/l]	6.4	10.1	8.6	7.8	6.2
pH	[ $\text{-}$ ]	7.4	7.6	7.3	7.5	7.4
Conductivity	[ $\mu\text{S}/\text{cm}$ ]	740	889	853	814	811
SS	[mg/l]	234	434	534	532	234
Settleable solids <sub>120</sub>	[ml/l]	12	30	34	28	30
Turbidity	[FNU]	152	239	215	259	246
Faecal coliforms	[1/100ml]	-	-	-	-	-
<b>Effluent:</b>						
COD <sub>hom</sub>	[mg/l]	34	34	66	54	43
COD <sub>fil</sub>	[mg/l]	17	24	37	49	28
BOD <sub>5</sub>	[mg/l]	3	4	5	5	3
NH <sub>4</sub> -N	[mg/l]	1.4	2.3	5.0	4.6	3.1
NO <sub>3</sub> -N	[mg/l]	18.5	24.2	25.8	18.2	21.5
NO <sub>2</sub> -N	[mg/l]	0.3	< 0.1	0.5	0.5	0.6
N <sub>inorg</sub>	[mg/l]	20.3	26.6	31.3	23.3	25.2
N <sub>tot</sub>	[mg/l]	21.5	31.0	33.3	27.3	28.0
P <sub>tot</sub>	[mg/l]	2.4	2.2	2.5	2.5	3.1
pH	[ $\text{-}$ ]	7.0	6.9	7.1	7.1	7.1
Conductivity	[ $\mu\text{S}/\text{cm}$ ]	548	650	686	651	651
SS	[mg/l]	6	6	9	9	10
Settleable solids <sub>120</sub>	[ml/l]	< 0.1	< 0.1	< 0.1	< 0.1	< 0.1
Turbidity	[FNU]	3.9	2.6	2.8	2.6	2.8
Faecal coliforms	[1/100ml]	-	-	-	-	-
<b>Biology:</b>						
Temperature	[°C]	8.4	6.9	8.5	8.5	7.9
SSV <sub>30</sub>	[ml/l]	215	300	420	420	750



MLSS	[g/l]	1.9	2.5	3.8	4.0	4.2
O <sub>2</sub>	[mg/l]	6.7	5.8	0.8	0.8	7.1

\*Power breakdown 31.12.07 from to 01.01.08

Table 5: Results from 24.01.2008 to 27.03.2008

Test schedule	3	5*	5	5	6
		100 %	100 %	100 %	150 %
Date	24.01.2008	21.02.2008	14.03.2008	20.03.2008	27.03.2008
Air Temperature min/max [°C]	3/5	-3/6	5/12	1/7	-3/9
<b>Influent:</b>					
Temperature	[°C]	9.8	8.9	11.6	8.8
COD	[mg/l]	568	439	595	724
BOD <sub>5</sub>	[mg/l]	178	191	202	374
NH <sub>4</sub> -N	[mg/l]	31.6	33.8	34.6	33.0
N <sub>tot</sub>	[mg/l]	43	47	48	51
P <sub>tot</sub>	[mg/l]	6.3	5.7	8.4	7.8
pH	[ $\text{-}$ ]	7.4	7.3	7.5	7.3
Conductivity	[ $\mu\text{S}/\text{cm}$ ]	796	847	890	872
SS	[mg/l]	304	216	228	442
Settleable solids <sub>120</sub>	[ml/l]	20	14	21	27
Turbidity	[FNU]	124	121	119	268
Faecal coliforms	[1/100ml]	-	-	-	-
<b>Effluent:</b>					
COD <sub>hom</sub>	[mg/l]	56	77	49	50
COD <sub>fil</sub>	[mg/l]	48	48	42	36
BOD <sub>5</sub>	[mg/l]	9	15	7	12
NH <sub>4</sub> -N	[mg/l]	5.5	14.9	4.4	5.3
NO <sub>3</sub> -N	[mg/l]	14.9	5.6	17.1	17.3
NO <sub>2</sub> -N	[mg/l]	1.4	1.8	0.8	1.3
N <sub>inorg</sub>	[mg/l]	21.8	22.3	22.3	23.9
N <sub>tot</sub>	[mg/l]	23.3	23.4	24.6	25.1
P <sub>tot</sub>	[mg/l]	2.9	3.3	3.3	3.4
pH	[ $\text{-}$ ]	7.2	7.2	7.1	7.1
Conductivity	[ $\mu\text{S}/\text{cm}$ ]	629	710	636	682
SS	[mg/l]	12	22	8	12
Settleable solids <sub>120</sub>	[ml/l]	< 0.1	1.5	0.1	0.5
Turbidity	[FNU]	5.3	6.5	6.6	9.3
Faecal coliforms	[1/100ml]	-	-	-	-
<b>Biology:</b>					



Temperature	[°C]	9.5	7.4	9.4	8.1	8.1
SSV <sub>30</sub>	[ml/l]	480	690	900	810	180
MLSS	[g/l]	4.2	6.5	7.0	5.2	1.5
O <sub>2</sub>	[mg/l]	6.5	6.3	1.9	3.4	3.6

\*First sample after sequence 4 "Low occupation stress / vacations"

Table 6: Results from 03.04.2008 to 08.05.2008

Test schedule	6	7	7	7	7
		150 %	100 %	100 %	100 % *PB
Date	03.04.2008	10.04.2008	17.04.2008	30.04.2008	08.05.2008
Air Temperature min/max	[°C]	5/12	1/12	-3/11	10/18
<b>Influent:</b>					
Temperature	[°C]	11.0	9.4	9.3	12.9
COD	[mg/l]	663	947	768	631
BOD <sub>5</sub>	[mg/l]	259	330	379	253
NH <sub>4</sub> -N	[mg/l]	34.8	30.4	31.6	35.8
N <sub>tot</sub>	[mg/l]	49	62	45	47
P <sub>tot</sub>	[mg/l]	7.5	9.9	6.7	6.9
pH	[ $\cdot$ ]	7.1	7.0	7.1	7.2
Conductivity	[ $\mu$ S/cm]	865	1082	907	870
SS	[mg/l]	450	512	548	318
Settleable solids <sub>120</sub>	[ml/l]	25	55	24	25
Turbidity	[FNU]	262	251	208	258
Faecal coliforms	[1/100ml]	-	-	-	-
<b>Effluent:</b>					
COD <sub>hom</sub>	[mg/l]	87	76	54	33
COD <sub>fil</sub>	[mg/l]	32	28	41	26
BOD <sub>5</sub>	[mg/l]	21	16	4	4
NH <sub>4</sub> -N	[mg/l]	1.9	1.4	1.3	1.3
NO <sub>3</sub> -N	[mg/l]	22.2	27.2	19.5	21.8
NO <sub>2</sub> -N	[mg/l]	0.5	0.4	0.4	0.8
N <sub>inorg</sub>	[mg/l]	24.6	29.0	21.2	23.9
N <sub>tot</sub>	[mg/l]	26.5	34.0	23.9	28.2
P <sub>tot</sub>	[mg/l]	3.1	3.7	3.2	3.2
pH	[ $\cdot$ ]	7.2	7.0	7.3	7.2
Conductivity	[ $\mu$ S/cm]	709	748	647	656
SS	[mg/l]	43	30	3	4
Settleable solids <sub>120</sub>	[ml/l]	2.5	2.5	0.1	< 0.1
Turbidity	[FNU]	18.1	18.8	5.7	2.7



Faecal coliforms	[1/100ml]	-	-	-	-	-
<b>Biology:</b>						
Temperature	[°C]	8.7	8.9	9.0	12.0	15.8
SSV <sub>30</sub>	[ml/l]	200	360	540	300	720
MLSS	[g/l]	2.0	2.7	3.9	3.6	4.0
O <sub>2</sub>	[mg/l]	5.3	1.1	7.4	1.2	6.2

\*Power breakdown from 21.04.08 to 22.04.08

Table 7: Results from 15.05.2008 to 19.06.2008

Test schedule	7	7	8	8	9	9
		100 %	50 %	50 %	100 %	100 %
Date	15.05.2008	21.05.2008	29.05.2008	12.06.2008	19.06.2008	
Air Temperature min/max	[°C]	13/25	5/21	15/25	8/21	7/18
<b>Influent:</b>						
Temperature	[°C]	17.8	14.2	16.0	16.7	16.0
COD	[mg/l]	936	774	979	648	816
BOD <sub>5</sub>	[mg/l]	390	349	442	234	356
NH <sub>4</sub> -N	[mg/l]	39.3	34.6	39.1	28.3	27.0
N <sub>tot</sub>	[mg/l]	55	54	60	55	41
P <sub>tot</sub>	[mg/l]	7.3	8.5	9.0	7.0	7.4
pH	[ $\cdot$ ]	7.0	6.9	7.1	7.1	6.7
Conductivity	[ $\mu$ S/cm]	961	973	922	912	909
SS	[mg/l]	500	418	404	322	446
Settleable solids <sub>120</sub>	[ml/l]	24	22	31	18	22
Turbidity	[FNU]	176	175	236	183	252
Faecal coliforms	[1/100ml]	-	-	-	-	-
<b>Effluent:</b>						
COD <sub>hom</sub>	[mg/l]	38	52	37	51	46
COD <sub>ri</sub>	[mg/l]	30	32	23	37	37
BOD <sub>5</sub>	[mg/l]	6	12	7	11	6
NH <sub>4</sub> -N	[mg/l]	6.2	5.2	2.0	21.7	21.9
NO <sub>3</sub> -N	[mg/l]	2.5	12.2	18.0	< 1.0	< 1.0
NO <sub>2</sub> -N	[mg/l]	1.2	0.7	0.5	< 0.1	< 0.1
N <sub>inorg</sub>	[mg/l]	9.9	18.1	20.5	22.3	22.0
N <sub>tot</sub>	[mg/l]	9.8	19.6	23.0	23.9	22.2
P <sub>tot</sub>	[mg/l]	4.1	3.7	4.1	3.8	3.0
pH	[ $\cdot$ ]	7.5	7.1	7.3	7.5	7.3
Conductivity	[ $\mu$ S/cm]	701	767	695	778	769
SS	[mg/l]	3	20	13	21	5



Settleable solids <sub>120</sub>	[ml/l]	0.1	1.3	0.1	< 0.1	< 0.1
Turbidity	[FNU]	4.1	11.7	9.9	9.0	4.1
Faecal coliforms	[1/100ml]	-	-	-	-	-
<b>Biology:</b>						
Temperature	[°C]	16.9	14.3	16.6	14.8	16.3
SSV <sub>30</sub>	[ml/l]	920	840	780	810	920
MLSS	[g/l]	5.9	5.2	5.4	8.2	9.4
O <sub>2</sub>	[mg/l]	0.2	4.8	4.9	5.9	0.5

Table 8: Results from 26.06.2008

<b>Test schedule</b>	9	
	100 %	
Date	26.06.2008	
Air Temperature min/max	[°C]	10/27
<b>Influent:</b>		
Temperature	[°C]	17.8
COD	[mg/l]	852
BOD <sub>5</sub>	[mg/l]	391
NH <sub>4</sub> -N	[mg/l]	25.2
N <sub>tot</sub>	[mg/l]	48
P <sub>tot</sub>	[mg/l]	8.4
pH	[ $\cdot$ ]	7.1
Conductivity	[ $\mu$ S/cm]	872
SS	[mg/l]	508
Settleable solids <sub>120</sub>	[ml/l]	19
Turbidity	[FNU]	211
Faecal coliforms	[1/100ml]	-
<b>Effluent:</b>		
COD <sub>hom</sub>	[mg/l]	62
COD <sub>fil</sub>	[mg/l]	31
BOD <sub>5</sub>	[mg/l]	13
NH <sub>4</sub> -N	[mg/l]	27.4
NO <sub>3</sub> -N	[mg/l]	< 1.0
NO <sub>2</sub> -N	[mg/l]	< 0.1
N <sub>inorg</sub>	[mg/l]	28.0
N <sub>tot</sub>	[mg/l]	27.8
P <sub>tot</sub>	[mg/l]	3.7
pH	[ $\cdot$ ]	7.6
Conductivity	[ $\mu$ S/cm]	750



SS	[mg/l]	27
Settleable solids $_{120}$	[ml/l]	0.1
Turbidity	[FNU]	13.8
Faecal coliforms	[1/100ml]	-
<b>Biology:</b>		
Temperature	[°C]	16.9
SSV $_{30}$	[ml/l]	930
MLSS	[g/l]	7.4
O $_2$	[mg/l]	0.0

## 5.2 Evaluation of the test sequences

The EN 12566-3 requires the evaluation of the 20 samples obtained in the sequences with 100 % daily hydraulic loading (test sequences 1, 3, 5, 7 and 9).

Mean, minimum and maximum values of the 20 effluent samples in the nominal phases as well as the appropriate standard deviations are shown in Table 9 and 10.

Table 9: treatment efficiencies for the nominal test sequences (100%)

Efficiency [%]	Mean*	Minimum	Maximum	Standard deviation
COD	92.8	82.5	95.9	2.9
BOD <sub>5</sub>	97.1	92.1	98.9	1.8
Ntot	49.2	39.0	82.2	9.9
NH <sub>4</sub> -N	74.6	0.0	96.4	28.0
Ptot	57.1	42.1	78.2	7.3
SS	96.7	89.8	99.5	2.6

Table 10: effluent characteristics for the nominal test sequences (100%)

Effluent	Mean	Minimum	Maximum	Standard deviation
COD [mg/l]	50	33	77	12.5
BOD <sub>5</sub> [mg/l]	8	3	16	4.0
N <sub>tot</sub> [mg/l]	26	10	34	5.5
NH <sub>4</sub> -N [mg/l]	7.7	1.3	27.4	7.7

\*Efficiency ratio for the treatment efficiency declaration according to EN 12566-3 chapter 6.3



NO <sub>3</sub> -N	[mg/l]	15.0	< 1.0	27.2	8.6
N <sub>inorg</sub>	[mg/l]	23.5	9.8	31.3	4.6
P <sub>tot</sub>	[mg/l]	3.3	2.2	4.1	0.5
SS	[mg/l]	12	3	30	8.3
Settleable solids	[ml/l]	0.3	< 0.1	2.5	0.6



According to the guideline on the treatment of municipal wastewater 91/271/EWG, Annex 1, Table 2, Annotation (3) the nitrogen requirements refer only to water temperatures of 12°C or more in the biological reactor. To correspond this fact with reference to the treatment of household wastewater in decentralised systems Table 11 shows the treatment efficiencies regarding the nitrogen parameters also only for water temperatures in the bioreactor of 12°C or more.

Table 11: nitrogen characteristics for water temperatures of 12°C or more in the bioreactor

	Mean*	Minimum	Maximum	Standard deviation
Efficiency N <sub>tot</sub> [%]	53.4	40.0	82.2	15.6
Efficiency NH <sub>4</sub> -N [%]	51.1	0.0	96.4	41.6
N <sub>tot</sub> [mg/l]	22.4	9.8	28.2	6.7
NH <sub>4</sub> -N [mg/l]	14.0	1.3	27.4	10.9
NO <sub>3</sub> -N [mg/l]	6.7	< 1.0	21.8	9.2
N <sub>inorg</sub> [mg/l]	21.1	9.9	28.0	6.1

Table 12 shows the efficiency for selected parameters in the test schedules with 50 % and 150 % hydraulic load (sequences 2, 6 and 8).

Table 12: efficiencies for 50% and 150% hydraulic daily load

	Test sequence					
	50 %	50 %	150 %	150 %	50 %	50 %
Date	06.12.2007	13.12.2007	27.03.2008	03.04.2008	21.05.2008	29.05.2008
Efficiency[%]						
COD	93.7	93.8	83.8	86.9	93.3	96.2
BOD <sub>5</sub>	97.6	98.5	81.2	91.9	96.6	98.4
N <sub>tot</sub>	46.5	46.0	43.4	45.6	63.7	61.7
NH <sub>4</sub> -N	92.5	94.0	89.3	94.4	85.0	94.9
P <sub>tot</sub>	60.8	62.5	53.5	58.7	56.5	54.4
SS	96.8	97.4	88.4	90.4	95.2	96.8


\*Efficiency ratio for the treatment efficiency declaration according to EN 12566-3 chapter 6.3



### 5.3 Graphical presentation

To display the treatment efficiency of the tested system more clearly, the results of all test sequences, including nominal load, hydraulic over- and underload, are graphically shown in this chapter. For clarification, the concentrations of the influent and effluent as well as the resulting efficiency are shown.

The concentrations of COD are shown in Figure 7.



The influent and effluent concentrations of  $\text{BOD}_5$  are shown in Figure 8.




Figure 8: BOD<sub>5</sub> influent and effluent concentrations

The percental efficiencies resulting from the inflow and outflow of  $BOD_5$  and COD are displayed in Figure 9.




Figure 9: Treatment efficiencies  $BOD_5$  and COD

Throughout the whole test (all sequences) the average treatment efficiencies of  $BOD_5$  and COD resulted as follows:

	%
COD	92.4
$BOD_5$	96.4

The percental efficiencies resulting from the inflow and outflow of ammonium, nitrate und inorganic nitrogen are shown in Figure 10.




Figure 10: NH<sub>4</sub>-N influent concentration and NH<sub>4</sub>-N, NO<sub>3</sub>-N and N<sub>inorg</sub> effluent concentration

The effluent results of NH<sub>4</sub>-N varied from 1.3 mg/l to 27.4 mg/l the entire test.

The treatment efficiencies of the nitrogen parameters are presented in Figure 11:




Figure 11: treatment efficiencies of NH<sub>4</sub>-N und N<sub>total</sub>

The average results of the parameters from Figure 11 for the complete test period are shown in the following table.

	%
NH <sub>4</sub> -N	78.5
N <sub>total</sub>	49.7

Figure 12 shows the concentrations of the filterable solids from the inlet and outlet of the ASP 06 treatment system.




Figure 12: SS influent and effluent concentrations

The resulting treatment efficiencies of SS and total phosphorus are shown in Figure 13.




Figure 13: treatment efficiencies of SS und P<sub>tot</sub>

The average treatment efficiencies of SS and P<sub>tot</sub> throughout the whole test were as follows:

	%
SS	96.1
P <sub>tot</sub>	57.3

## **6 Assessment of the general plant safety**

### **6.1 Operational safety of system components**

An alarm signal as requested by the EN 12566-3 was not existent for the tested treatment plant. The manufacturer declares that he has changed the blower design on all plants of the range to incorporate the alarm function.

There were no mechanical or electrical malfunctions during the whole 38-week test procedure.

### **6.2 Sludge removal**

Throughout the complete 38-week test period a sludge removal was not necessary.

### **6.3 Maintenance and self-checking**

Time and effort for maintenance and self-checking for the tested ASP 06 treatment system meet the usual time and effort for a small sewage treatment plant.

### **6.4 Accessibility**


All plant components were accessible in a satisfactory way. There is one access manhole on the tank top. The size of its cover is 75 cm x 75 cm.



## 7 Annex

Technical drawings and information about the sizing and design of the ASP 06 small wastewater treatment system (manufacturer's information):



**Manufacturer's information**

**Manufacturer's information**

Plant: ASP 6 to 20PE					
<b>Process Calculations</b>					
Compiled By:	Alan Ford	Date:	Jan-08		
<b>INPUT DATA</b>					
<b>Plant Size Range</b>					
6PE					
12PE					
16PE					
20PE					
<b>Design Flows and Loads</b>					
Item	Flow l/d	BOD g/d	BOD mg/l	NH3 g/d	NH3 mg/l
Per Capita	200	60	300	8	40
	<i>m3/d</i>	<i>kg/d</i>		<i>kg/d</i>	
6PE	1.2	0.36		0.048	
12PE	2.4	0.72		0.096	
16PE	3.2	0.96		0.128	
20PE	4	1.2		0.16	
Note: Peak hourly flow = 3 x design flow - for a maximum period of 2 hours					
<b>Design Discharge Consent</b>					
Plant to achieve	20:30:20	BOD:SS:NH3/4			
<b>Plant Volumes &amp; Areas</b>					
Inner Biozone	Outer Biozone	Total Biozone	Settlement Volume	Settlement Area	
<i>m3</i>	<i>m3</i>	<i>m3</i>	<i>m3</i>	<i>m2</i>	
6PE	0.8	0.147	0.947	0.876	1.2
12PE	1.139	0.147	1.286	1.264	1.2
16PE	1.252	0.147	1.399	1.393	1.2
20PE	1.365	0.147	1.512	1.522	1.2
<b>Plant Operating Range</b>					
MLSS		2500 - 15000 mg/l			
Temperature (effluent)		10 - 20 degrees C			
<b>Plant Airflow Rates</b>					
	<i>m3/h</i>				
6PE	6				
12PE	7.8				
16PE	9.6				
20PE	12				



**Manufacturer's information**

<b>Plant: ASP 6 to 20PE</b>				
<b>Process Calculations</b>				
Compiled By:	Alan Ford	Date:	Jan-08	
<b>PROCESS DESIGN</b>				
<b>Biozone Design</b>				
<b>Design Basis</b>				
1.	Calculate required minimum biozone volume based on required f:m loading with minimum MLSS concentration @ compare with actual volumes			
2.	Calculate actual f:m at minimum & maximum MLSS concentrations			
3.	Calculate biozone plant hydraulic retention time			
4.	Calculate maximum oxygen requirement @ maximum MLSS concentration			
5.	Calculate oxygen provided and compare with 4.			
1.				
Minimum f:m ratio to achieve final effluent consent	=	0.33		
Minimum MLSS concentration	=	2500 mg/l		
<b>BOD</b>				
<i>f</i>				
6PE	0.36	0.44	0.947	
12PE	0.72	0.87	1.286	
16PE	0.96	1.16	1.399	
20PE	1.2	1.455	1.512	
2.				
Maximum MLSS concentration	=	15000 mg/l		
<b>Actual Volume</b>				
<i>m3</i>				
<b>maximum actual</b>				
<i>f:m</i>				
6PE	0.947	0.15	0.03	
12PE	1.286	0.22	0.04	
16PE	1.399	0.27	0.05	
20PE	1.512	0.32	0.05	
3.				
<b>Actual Volume</b>				
<i>m3</i>				
<b>Flow</b>				
<i>m3/d</i>				
<b>Hydraulic Retention</b>				
<i>Hours</i>				
6PE	0.947	1.2	18.94	Retention Sufficient
12PE	1.286	2.4	12.86	Retention Sufficient
16PE	1.399	3.2	10.4925	Retention Sufficient
20PE	1.512	4	9.072	Retention Sufficient

**Manufacturer's information**

Plant: ASP 6 to 20PE							
<b>Process Calculations</b>						 <b>conder</b> ENVIRONMENTAL SOLUTIONS	
Compiled By:	Alan Ford	Date:	Jan-08				
4.							
Oxygen requirement @ 20 degrees C and 15,000mg/l MLSS							
	=	(0.6 x BOD) + [4.57 x (NH3 - 10% (cell mass) - effluent NH3)] x (0.05 x MLVSS)					
	BOD	BOD	NH3	Net NH3	NH3	MLVSS	O2
	pf			pf	pf	MLVSS	Requirement
	kg/d		kg/d	kg/d	kg/d	ratio	kg/d
6PE	0.36	1.1	0.048	0.031	1.1	0.6	0.82
12PE	0.72	1.1	0.096	0.062	1.1	0.6	1.37
16PE	0.96	1.1	0.120	0.083	1.1	0.6	1.68
20PE	1.2	1.1	0.16	0.104	1.1	0.6	2
pf = peaking factor							
5.							
	Air	Oxygen	Diffuser Efficiency	Diffuser		Alpha	Oxygen
Provided	Provided	Clean Water	Submergence		Factor	Transferred	
	m3/d	kg/d	% / m submergence			kg/d	
6PE	144	40.09	2.5	1.262		0.7	0.89 OK
12PE	187.2	52.12	2.5	1.562		0.7	1.42 OK
16PE	230.4	64.14	2.5	1.662		0.7	1.87 OK
20PE	288	80.18	2.5	1.762		0.7	2.47 OK
Settlement Zone Design							
1.	Calculate settlement zone rise rate & retention - compare with required - normal flow condition						
	Normal Flow	Zone Area	Zone Volume	Actual Rise Rate	Required Rise Rate		
	m3/d	m2	m3	m/h	m/h	h	h
6PE	1.2	1.2	0.876	0.04	0.7	OK	17.5 2 OK
12PE	2.4	1.2	1.264	0.08	0.7	OK	12.6 2 OK
16PE	3.2	1.2	1.393	0.11	0.7	OK	10.4 2 OK
20PE	4	1.2	1.522	0.14	0.7	OK	9.1 2 OK
Calculate settlement zone rise rate & retention - compare with required - peak flow condition							
	Peak Flow	Zone Area	Zone Volume	Actual Rise Rate	Required Rise Rate		
	m3/d	m2	m3	m/h	m/h	h	h
6PE	3.6	1.2	0.876	0.13	0.7	OK	5.8 2 OK
12PE	7.2	1.2	1.264	0.25	0.7	OK	4.2 2 OK
16PE	9.6	1.2	1.393	0.33	0.7	OK	3.5 2 OK
20PE	12	1.2	1.522	0.42	0.7	OK	3 2 OK



## Manufacturer's information



### Regulations & your responsibilities

A package sewage treatment plant is an essential component of the home or workplace. It provides safe and hygienic wastewater treatment and disposal to make sure your family and colleagues have a pleasant place to live and work and that the local community and environment is protected. So you must treat your package sewage treatment plant with the respect it deserves and make sure it is operated and maintained properly so it can continue to provide outstanding performance.

#### Building regulations

- 1.0 Notices are required to be displayed in the household stating that the plant is connected to a private treatment plant. Notices in toilets and bathrooms would also inform guests.
- 2.0 Planning and building control departments of your local council should be informed of the work being undertaken.

#### What responsibilities do I have?

- 3.0 Users of a packaged treatment plant have a responsibility under the terms of the Water Resources Act (1991) to ensure that the plant meets the standards set by the Environment Agency. This plant is designed to ensure that the final effluent discharge back into the water body (Ground Water) or watercourse meets these requirements. Once your plant is commissioned and operating efficiently, the Environment Agency may sample the discharge from the plant to check it meets the agreed standards. The Environment Agency also has the right to enter the consent standard every two years. It is therefore essential to regularly maintain and service the plant to make sure it is running efficiently. You can do a lot to ensure you get the best out of your plant. This manual offers a simple and practical guide to help you do just that!
- 4.0 The plant must be emptied of sludge as required by the operating instructions, ensuring that the waste is disposed of by a licensed company that is licensed to do so. All documentation relating to the sludge disposal should be kept with the servicing records.
- 5.0 The plant must be serviced in accordance with the operation and maintenance manual. The annual service must be carried out by an approved service provider. Record of all services must be kept by the consumer.
- 6.0 When a house is sold evidence that the treatment plant has been properly installed and maintained will be required.



No 5382

17/07/2014 14:26:29

2



### Installation, Operating and Maintenance Manual

For

#### Cleerflo ASP Package Sewage Treatment Plants

Discharge consent:

20BOD1055S220NH3-H4



Unit installed  
(please tick)

ASP06   
ASP12   
ASP16   
ASP20

Note to the End User  
Householders are guided to read the sections in the yellow boxes on pages 2 and pages 26 to 31.

#### Approved Service Provider



Tel: 08704 050902  
Fax: 08704 050903  
Email: [enquiries@hydroserve.net](mailto:enquiries@hydroserve.net)  
Web: [www.hydroserve.net](http://www.hydroserve.net)

Convera Products Limited, 2 Whitehouse Way, Solihull, West Midlands, B90 2HZ  
Tel: 0870 254 0044 Fax: 0870 254 0005  
Email: [sales@converaproducts.com](mailto:sales@converaproducts.com) Web: [www.converaproducts.com](http://www.converaproducts.com)



No 5382

17/07/2014 14:26:29

3



## Manufacturer's information



Client ID: 00000000000000000000



Client ID: 00000000000000000000

### Table of Contents

#### What's included in this manual?

#### Introduction

#### Health and Safety

#### Health

#### Safety

#### Process and Plant Description

#### Installation Guide

#### General Installation Procedure

#### Start-up and Commissioning

#### Maintenance Schedule

#### Appendix A: ASP Specification & CE mark

#### Appendix B: Compressors details

#### Appendix C: Serviceability test & employing standards

#### Appendix D: Fault finding

#### Appendix E: Household procedures (Do & Don't)

#### Do's and Don'ts

#### Appendix F: Extension kit instructions

#### Appendix G: Quick Installation Guide

### Introduction

This installation, Operation and Maintenance (O&M) manual includes descriptive literature, specifications and drawings relating to the principal mechanical and electrical equipment incorporated in the unit. It is the responsibility of the installer and operator to read and fully understand these instructions before installing, commissioning or operating the plant. In the unlikely event of problems occurring with your plant you may either refer to this manual, your equipment supplier or directly to Condar Products Ltd.

The plant comprises two treatment stages: an aerobic biological zone and a final clarification zone. The design combines the benefits of a well proven treatment process with our engineering expertise to produce a high quality system which is robust and reliable. The plant will provide long and trouble free operation providing the simple maintenance procedures laid out in this manual are regularly carried out.

Your attention is drawn to the 'Health and Safety' section at the beginning of this manual. It is IMPERATIVE that you read these instructions BEFORE working on the plant.

The plant has been designed to treat the volume and strength of sewage specified in the original quotation. Please note the following points:

- The maximum design loading must not be exceeded (see original quotation and order acknowledgement for details).
- The plant is designed for gravity feed and should not be pumped to.
- Surface water, non treated, must not enter the plant and/or drainage system.
- High volume discharges from swimming pools or leisure must not enter the plant.
- Large quantities of chemicals such as water softener regenerant, disinfectants, strong acids or alkalis, oil and grease, pesticides or photographic chemicals must not enter the system.

- Do not use chemical or biological emulsifiers in grease traps.
- Do not dispose of nappies, sanitary towels and incontinence pads via the toilet.
- Do not dispose of medicines down the toilet or sink.
- Waste disposal units should not be used unless accounted for within the original specification.

If you have any doubt about a particular substance, please contact Condar Products Ltd.



Ref ID: PIA2008-086B25.02

3

4



Ref ID: PIA2008-086B25.02

Approved by  
Assessor No. 1234

## Manufacturer's information



PRODUCTS

CARES UP OWN LINE GUARANTEE

How can I prevent it? → After having worked in contact with sewage or anything contaminated with sewage, wash your hands and forearms thoroughly with soap and water. If your clothes, boots or tools are contaminated with sewage, wash thoroughly after handling them.

- Take immediate action to wash thoroughly any cut, scratch or abrasion of the skin as soon as possible. Apply antibiotic to the wound, cover with cotton wool or gauze, and protect with a waterproof plaster.
  - DO NOT handle food, drink or smoking materials without first washing your hands.
- If you contract the symptoms described above after coming into contact with sewage, report it to your doctor immediately and advise him/her of the circumstances.

### Safety

Sewage gases are potentially hazardous. DO NOT enter the unit or any sump.

Before carrying out any maintenance work, the equipment must be electrically isolated by unplugging the power socket!

DO NOT leave manways open for any longer than is necessary. Temporary barriers and warning signs should be erected around any open covers or manways as appropriate.

### Health

The following is extracted from a health warning card supplied to Conder Products staff. It is the client's responsibility to ensure that all necessary protective clothing/equipment is available.

#### Leptospirosis - What is Leptospirosis and are you at risk?

Two types of leptospiral infection exist people in the UK:

1. Water Disease - this is a serious and sometimes fatal infection that is transmitted to humans by contact with soil, water or sewage contaminated with urine from infected rats.
2. Hard-type Leptospirosis - this is transmitted from cattle to humans

What are the symptoms? → Both diseases start with a flu-like illness with a persistent and severe headache, muscle pains and vomiting. Jaundice appears about the 7th day of the illness.

How might I catch it? → The bacteria can enter the body via cuts and sores and through the lining of the mouth and throat or through the eyes.



IEC 60335-2-20/EN 60335-2-20/BS 7233-2-20



EU Directive 2002/95/EC

6



PRODUCTS

CARES UP OWN LINE GUARANTEE

## Health and Safety

### (Important - Please Read This Before Starting Any Work on the Plant)

United Kingdom: Health and Safety at Work Act 1974

Section 5(a) of this Act requires manufacturers to advise their customers on the safety and the handling precautions to be observed when installing, operating, maintaining and servicing their products.

This user's instruction is therefore drawn to the following:

1. The appropriate sections of this manual must be read before working on the equipment.
2. Installation and servicing must only be carried out by suitably trained or qualified personnel.
3. Normal safety precautions must be taken and appropriate procedures observed to avoid accidents.

Refer to Conder Products Ltd or your local supplier for technical advice or product information.

### Health

The following is extracted from a health warning card supplied to Conder Products staff. It is the client's responsibility to ensure that all necessary protective clothing/equipment is available.

#### Leptospirosis - What is Leptospirosis and are you at risk?

Two types of leptospiral infection exist people in the UK:

1. Water Disease - this is a serious and sometimes fatal infection that is transmitted to humans by contact with soil, water or sewage contaminated with urine from infected rats.
2. Hard-type Leptospirosis - this is transmitted from cattle to humans

What are the symptoms? → Both diseases start with a flu-like illness with a persistent and severe headache, muscle pains and vomiting. Jaundice appears about the 7th day of the illness.

How might I catch it? → The bacteria can enter the body via cuts and sores and through the lining of the mouth and throat or through the eyes.

5



## Manufacturer's information



### Owner's responsibilities


The owner of the Sewage Treatment Plant is entirely responsible for plant operation and ensuring that the effluent quality does not breach the Discharge Consent Standards.

The offloading of the treatment plant and the correct installation is the responsibility of the owner. We would strongly recommend that the plant should be installed by a contractor that understands sewage and drainage systems. The chosen method of discharge remains with the client in consultation with the environment agency. The design, installation and maintenance of the same remains with the client. Condar Products accept no liability for any damage or loss, including consequential loss, caused by the failure of any pumping equipment.

### Process and Plant Description

The Cisalfo ASO treatment plants have an inner central chamber and an outer settlement tank. The plant runs aseptically using the established septic tank principle in the central bio-zone chamber. A simple coarse bubble diffuser housed in draft tube introduces the air that provides the oxygen to the bacteria that then treats the sewage. The bio-zone retains the mixture of water, sewage and air until a level of treatment has been achieved. The treated effluent then enters the conical clarifier tank where sedimentation takes place and the settled solids are drawn back towards the draft tube with the diffuser in it and returned to the bio-zone. The effluent finally leaves the plant over a weir that extends around the circumference of the tank at the outlet level. The movement of fluid through the whole system is by gravity displacement. There are no moving parts in the treatment plant.

- A) Inlet flow from the house (a)
- B) Zone chamber
- C) Flow around the draft tube
- D) Treated effluent being settled
- E) Settled bio-solids returning to the draft tube
- F) Final effluent going over the weir
- G) Effluent leaving the plant



6



7

**Manufacturer's information**

CHIEF AD OUTLINE G.JANNE DEC

**Installation Guide****IMPORTANT! PLEASE READ HEALTH AND SAFETY INSTRUCTIONS BEFORE ATTEMPTING ANY WORK**

The following instructions are offered for guidance only. Contact a suitably experienced and qualified ground worker for site specific assistance.

**Materials**

**It is strongly recommended that concrete and/or backfill materials are not ordered until the treatment plant is on site. No liability will be accepted for losses incurred by the unlikely event of a late delivery of the treatment plant.**

**Offloading**

The contractor is responsible for offloading the tank and any accessories using one of the following two methods:

- Using straps through the eyelets. Any chains or steel ropes used in rigging must not be in contact with the tank)
- Using a forklift through the poly-deck pallet

**Do not lift the tank if it contains any water. Wash off the tank when lifting by using guide ropes. Do not allow the tank to impact against other objects. If the tank is stored on site prior to installation, it must be upright on a flat and level ground where it cannot be punctured or otherwise damaged. Check with tank or other cushioning material to prevent moving and to down if high winds are expected.**

**Supplied Items**


The usual extent of supply is:

- (i) Treatment plant ready for installation.
- (ii) Housing and an compressor
- (iii) Air hoses (10m) and connections
- (iv) Installation, operation and maintenance manual
- (v) Compressor manual

See delivery note for items ordered.



CHIEF AD OUTLINE G.JANNE DEC



Clercific Unit	ASP06	ASP12	ASP16	ASP20
Population Equivalent	6	12	16	20
Hydraulic Load (l/day)	1200	2400	3200	4000
Organic Load (g BOD <sub>5</sub> per day)	360	720	960	1200
NH <sub>3</sub> (g per day)	48	96	128	160
Dia. diameter (mm)	A	2080	2080	2080
Standard Net Weight (mm)	B	780	780	780
Inset Invert To Base (mm)	C	1570	1870	1970
Outlet Invert To Base	D	1470	1770	1970
Outlet Depth (mm)	E	2550	2650	2750
Pipework Fitting (mm)	110	110	110	110
Max Rated Power (Watts)	135	225	225	300
Estimated power consumption at working pressure (Watts)	100	170	165	220
Cover Size	750 SQ 230kg	750 SQ 260kg	750 SQ 300kg	750 SQ 360kg
Farm Weight				



REF ID: 2009-2000

9

REF ID: 2009-2000

10



## Manufacturer's information



Conder ADP 5000 G (AMM 2002)

### General Installation Procedure

Installation procedures must be in accordance with the Health and Safety at Work Act 1974, and other relevant legislation. Your procedures must also align with good building practice.

The specification for the concrete mix to surround the tank may be taken from BS 5328 : Part 1 : 1991 (including amendments), taking into account the site conditions and application requirements. For a typical non-structural application in non-aggressive soils a Standard Mix, S14 with a 5mm slump is generally suitable but also permits the equivalent Designation Mix, GEM3 can be specified as an alternative. If for non-typical applications, structural or other reasons, a higher than normal designation is required, the purchaser of the fresh concrete can use table 6 in BS 5328: Part 2: 1991 [amendment 875/9/October 1995] for guidance.

#### Lift height (rate of fall)

Determine the lift height [m], or rate of rise [m/h] for the specific concrete type used, to ensure that a design pressure [Pa] of 25kPa<sup>2</sup> on the tank is not exceeded.

#### Vibration

The design of the tank assures minimal compaction of the surrounding concrete. Where necessary, this may be extended to include careful use of 'light internal vibration'. Never use deep vibration which will substantially increase the pressure on the tank, possibly causing failure.

#### Impact of Concrete on Discharge

The effects of impact on discharge are considerable. These are controlled by the vertical form height, the tank diameter and the method of discharge. Under no circumstances should concrete be discharged directly onto the tank.

#### Loadings

If the tank is situated in an area where traffic or other superimposed loadings can be applied, it may be necessary to consult a structural engineer for the design of a reinforced concrete slab to prevent the load being transmitted to the tank (or its concrete surrounds). If this slab is constructed immediately above the tank, it should be separated from the concrete surrounding

#### Ventilation

Before installing the tank, care has to be given on how to provide adequate ventilation across the plant. As each site is different we can offer the following advice as guidance only (see BS201, BS6297 and Building Regulation Section H for further details). Ensure that an existing vent stack is in place or is supplied to the building serving the treatment plant.

**During installation it is important to check that the treatment plant remains level across all planes. The performance of a mis-aligned unit may be affected.**

1. The installer must determine the existence, or otherwise, of a water table taking into account the conditions at the time. Excavate to the tank dimensions allowing a minimum clearance of 250mm between the tank and the sides of the excavation. The depth of the excavation will be determined by the minimum invert levels and the tank dimensions. The base of the unit should sit on a firm leveled surface. **Important – the base should be level across all planes.** Care should be taken not to dig too deep a hole.

#### For deep invert installation, install the plant as below and consult appendix

2. If the installer is confident that the water table, at any time of the year, is not an issue then the backfill material may be sand, small rounded gravel or other such inert material at the discretion of the installer. The plant must be anchored by means of a minimum 200mm deep lean mix concrete poured over and between the base framework of the treatment plant.  
**Important – check that the treatment plant is level across all planes during installation.**  
If in doubt then assume a water table will be present and install and backfill appropriately.
3. It is recommended that the hole is excavated to a diameter of 1.9m - 2.0m. Measure approximately 850mm from the bottom and widen the hole to a diameter of 2.5m - 2.6m. See table on [Page 9](#).
4. It is recommended that the hole is excavated to a diameter of 1.9m - 2.0m. Measure approximately 850mm from the bottom and widen the hole to a diameter of 2.5m - 2.6m. See table on [Page 9](#).



BSI Approved Product



CE Marking



Concrete Specification

The specification for the concrete mix to surround the tank may be taken from BS 5328 : Part 1 : 1991 (including amendments), taking into account the site conditions and application requirements. For a typical non-structural application in non-aggressive soils a Standard Mix, S14 with a 5mm slump is generally suitable but also permits the equivalent Designation Mix, GEM3 can be specified as an alternative. If for non-typical applications, structural or other reasons, a higher than normal designation is required, the purchaser of the fresh concrete can use table 6 in BS 5328: Part 2: 1991 [amendment 875/9/October 1995] for guidance.

#### Lift height (rate of fall)

Determine the lift height [m], or rate of rise [m/h] for the specific concrete type used, to ensure that a design pressure [Pa] of 25kPa<sup>2</sup> on the tank is not exceeded.

#### Vibration

The design of the tank assures minimal compaction of the surrounding concrete. Where necessary, this may be extended to include careful use of 'light internal vibration'. Never use deep vibration which will substantially increase the pressure on the tank, possibly causing failure.

#### Impact of Concrete on Discharge

The effects of impact on discharge are considerable. These are controlled by the vertical form height, the tank diameter and the method of discharge. Under no circumstances should concrete be discharged directly onto the tank.

#### Loadings

If the tank is situated in an area where traffic or other superimposed loadings can be applied, it may be necessary to consult a structural engineer for the design of a reinforced concrete slab to prevent the load being transmitted to the tank (or its concrete surrounds). If this slab is constructed immediately above the tank, it should be separated from the concrete surrounding

#### Ventilation

Before installing the tank, care has to be given on how to provide adequate ventilation across the plant. As each site is different we can offer the following advice as guidance only (see BS201, BS6297 and Building Regulation Section H for further details). Ensure that an existing vent stack is in place or is supplied to the building serving the treatment plant.




**Manufacturer's information**

Chemical Air Duct Unit G-AU000002  
Blower housing installation.



Chemical Air Duct Unit G-AU000002



1. The air compressor is supplied in a green hose which will need a 13 amp single phase electrical supply. The housing should be within 10 metres of the treatment plant to allow the air hose to connect to the treatment point.
2. It is important not to locate the housing in direct sunlight, a shady place is preferred as this will extend the life of the compressor. We strongly recommend that an outside building or garage is used with plenty of space around the housing.
3. The housing needs to be placed on a firm base.
4. If the housing has to be installed outside then we do not recommend it should be done in a flower bed or where soil is exposed. Plants must not block the ventilation around the head of the housing or over the dome on the top. Pollen and dust may require the filter on the compressor to be cleaned more often.
5. Note if the compressor overheats due to poor installation it may invalidate the warranty.
6. Access to the housing is required for periodic maintenance. Locating the housing away from areas that may flood is essential.
7. The air hose (10m supplied) needs to be placed in a duct (typically at least 50mm diameter hard plastic pipe) so that the air hose is not squashed or bent. When the air hose needs replacing, having it in a duct enables easy replacement.
8. Do not forget to place a drain fitting in the duct.
9. Cut a hole in the duct pipe in the upper lid. In the flat section above the trim that joins the bows and upper parts of the tank together. Slide the duct through the hole allowing 50mm to project into the inside of the tank. Seal the gap between the duct pipe and the tank with a suitable silicone or acrylic sealant.
10. The cover end of the duct should finish by the housing.
11. The authorities will probably insist upon an efficient sampling point downstream of the treatment point, for which Conder can supply a Sample Chamber. Please contact Conder on 0370 252 0004 for details.



CE 0303  
RoHS 2002/95/EC



CE 0303  
RoHS 2002/95/EC

14



## Manufacturer's information



CHINE AP CALM LINE GRANDEUR

### Electrical Installation


In order to achieve a safe and cost effective installation, it is not possible to state a specific installation configuration that would suit all sites. The selection of current protection devices must remain the responsibility of the installer as the person qualified to assess site conditions and supply configuration. It is therefore imperative that detailed insulation of this equipment is left to a fully qualified electrician.

When installing the electrical supply the following points should be considered:

1. The supply to the unit should be provided by a dedicated circuit via isolation and protection devices consistent with the requirements for fixed equipment and in accordance with the latest regulations issued by the Institute of Electrical Engineers.
2. The supply to the unit should be an independent single phase 13-amp supply that can be isolated and has some form of protection.

Failure to comply with the following could result in the invalidation of warranty:

3. All connections to the compressor should be made via the enclosure using correctly sized and rated glands. Ensure the glands (supplied by others) and ducts are sealed to prevent the ingress of moisture and rodents.
4. When drilling the housing care must be taken to prevent the ingress of sand into the electrical components, air line or compressor.



Cleaner Air Clean Line GRANDEUR

11. Drill a hole in the housing just larger than the diameter of the air hose.
12. Pass the air hose from the treatment plant to the compressor.
13. Secure one end of the air hose to the connection in the treatment plant with a jubilee clip.
14. Check that the air hose is not bent, kinked or squashed and then connect the hose to the compressor with a jubilee clip.
15. Seal the ducts with suitable expanding foam to stop rodents or insects entering the duct.



CE MARKING

RoHS COMPLIANT



CE MARKING

RoHS COMPLIANT



## Manufacturer's information



Checklist APP CLEAR line • G-1A-N000002  
Shutdown Procedure

### Start-up and Commissioning

The unit **MUST** be commissioned before sewage is allowed to enter the system.  
Electrical connections and cabling should be checked by a qualified electrician.

Check that flush-line from the Compenser to the plant is unobstructed

Ensure there is no dirt or materials in the tank.

Ensure the unit is filled with clean water and there is a discharge from the outlet.  
This is best done by using a hosepipe in the intermediate or by running several taps in the connected household(s).

Check the electrical supply has been installed by a qualified electrician

Switching the isolator to the ON. Check the aeration pattern in the bio-zone

Checked by.....

Signature .....

Date.....

The Treatment Plant is now operational. However, the process relies on the growth of microorganisms in the Biological Zone. The time taken for these naturally occurring organisms to develop is dependent on temperature and is typically 8-10 weeks. However, this may be up to six months in winter. When the biology has 'matured' in this way, the treatment process will be completely established. During this time, do not allow any strong cleaning agents or bleaches to enter the system.

17



Checklist APP CLEAR line • G-1A-N000002

Temporary absence of flow will not be detrimental as the plant will continue to receive the activated sludge within the system. However, in circumstances where the flow may be interrupted for more than 2 MONTHS, the plant should be shutdown by the following procedure:

De-sludge the system in accordance with the instructions in the Appendix C section of this manual

Refill the system with clean water as described on previous page

Switch off the mains supply to the biowet.

### WARRANTY

5 year parts and Workmanship guarantee on the Biowet and Plant respectively. The Biowet supplied with your Treatment Plant contains serviceable parts. These **MUST** be replaced in line with the maintenance guide supplied by a qualified person. Failure to comply with the above Terms and Conditions will invalidate the warranty. Proof of purchase of parts and servicing MUST be retained in the event of any warranty claim.

Approved Service Specialists, Hydroserve (tel: 0870 169 0007).

Date replaced.....

Stamp \_\_\_\_\_



02/08/2009



02/08/2009



## Manufacturer's information



Client ID: GRANDE G-14000002

- Inspect the top surface of the biozone for any grease balls, soap suds, foaming or any non biodegradable materials. These materials are best removed from the plant and correctly disposed of.

- Check that the air supply is operating in the correct pressure range of 300mb - 450mb.

The compressors should be checked, see appendix B.

- Remove any soot from the outer calibration chamber and paper it carefully in the inner biozone chamber.

- Check that all the airways to the housing are clear and the compressor has adequate ventilation.

- Clean the blower air filter.

- Check that the air pipe from the compressor to the plant is not blocked, crushed or kinked.

- Ensure that all the bolts and nuts are correctly secured before leaving site.

- Check that the air diffuser is operating by inspecting the bio-zone substrate. We recommend that the diffuser is removed and cleaned annually as this may block in hard water deposits with scale.

### Every 2 ½ years

- Declog the plant.
- Carry out maintenance on the blower unit in accordance with the manufacturers instruction. The diaphragm should be replaced every 2 ½ years.

## Maintenance Schedule



Client ID: GRANDE G-14000002

### Weekly Inspections

- Check that the compressor is operating by listening to a gentle hum.
  - Check the final effluent discharging from the unit at the sample point. If it is cloudy or contains suspended particles contact your maintenance provider.
- 6 Monthly Check (or as stated otherwise)**
- We recommend that the unit is checked by an approved service technician at the first 6 monthly check.
- As for weekly, plus:
- Any signs that the compressor is overheating.
  - Air leaks and excessive heat in the air line and the fittings are secure.
  - Is there any evidence of water or moisture entering the housing
  - Check the aeration chamber has a vigorous air supply
  - Are there any foul odours when the lid is lifted.

If this is the first 6 month check, then carry out the annual service at the same time.

### Year service

Conder recommend that the yearly service be carried out by an approved service technician

### As for 6 monthly plus

- Obtain a sample of the final effluent to check that the plant is operating correctly. This may require introducing a small flow into the treatment unit to obtain the sample. It is important that this procedure is done before anything else.
- If the discharge is into a watercourse such as a stream or ditch then check for any visible signs of pollution. If the discharge is to a drainage field then check that it assesses the effluent from the plant is seeping into the ground.
- The activated sludge should be inspected to determine the settle ability of the sludge see appendix C. The settle ability test will determine when the plant needs emptying of sludge (desludging).

ISO 9001  
certifiedISO 14001  
certified

**Manufacturer's information**

Classe A IP CLASS 1000 C.J.2000 doc.

**Appendix A: ASP Specification & CE mark**

Catello CI Unit	ASP 06	ASP 12	ASP 16	ASP 20
Design Loadings (max.)				
Population Equivalent (PE)	6	12	16	20
Hydraulic Load (l/min)	1200	2400	4000	6000
Capacity (l/min)	360	720	1200	1440
Settleability (days)				
Dimensions	See page 5 for dimensions			
Drainage (max. height) m)	See page 5 for dimensions			
Depth (from inlet manif. m)	See page 9 for dimensions			
Fixing Flange	110 Socket			
Applicable Weight (empty) kg.	200	280	370	390
Blower				
Power consumption	See page 9 for details			
Power Supply	Single Phase 240V 50/60Hz			

Classe A IP CLASS 1000 C.J.2000 doc.

**Appendix B: Compressors details**

Refer to installation manual supplied

**Appendix C: Settle ability test & emptying sludge****Settle ability test.**

Take a turbidity tube or transparent 1 litre cylinder (jar can be used) with 10 equal dividers up the vertical side. Then follow the next sequence:

- Fit the tube with the liquor taken from the central activated biozone.
- Allow to stand and observe over a period of 30 minutes.
- The sludge should settle into a layer at the bottom and above this sludge layer should be clear liquid.

D) In ideal circumstances the colour of the sludge should be brown towards a coffee colour and settlement should usually occur within 10 to 15 minutes. The supernatant (clearer liquid above the sludge) should not be cloudy or have any large suspended particles in it. There should be no offensive odour.

**Settlement test/trouble shooting guide.**

Colour Grey. There may be too much laundry effluent going into the plants. Ask the residents to check they are not putting in too much detergent. Check that the laundry uses its not all on one day of the week and it is spread out. Try to limit the use to 1 to 2 clothes washings per day. Another possibility is that surface water from the roof etc. is entering the plant.

White deposits in the activated sludge. These are probably due to growth and it's going into the plant, which should be discouraged. The deposit may form into balls.

Light Brown. This is due either to the plant just starting up or that it is lightly loaded. The settlement may be poor and 'fuffy' in texture. To not confuse the lack of settle ability with the need to desludge the plant, in a lightly loaded plant this is not the right action to take.

Black colour. The plant may have some septic sludge in it. In this case the best solution is to have the plant desludged.



CE

21

22



WEEE

WEEE



**Manufacturer's information**

Chambre ADI CALM INN G.JANIN 0000



Chambre ADI CALM INN G.JANIN 0000

No clean supernatant if there is only a small amount of cloudy liquid above the sludge layer, 3 or 4 cm.  
If the container is divided into 10 parts vertically, then the unit needs emptying of sludge.

A record of five test and the results should be kept:

**Emptying the plant of sludge (de-sludging)**

Note: If a water table is present or local flooding has taken place then we recommend that the plant is not emptied at this time.

The procedure is as follows:

- A) Turn off the compressor.
- B) Remove the access cover above the plant.
- C) If access is obstructed remove the stay with the compressor in.
- D) The hose removing the sludge should be gently lowered into the plant taking care not to let the hose go down the central drain tube.
- E) The hose should rest on the bottom of the cone.
- F) The liquid should then be removed from the tank. When the level drops the slant lever from the clarifier will be removed. It may require a fresh water hose to help it flush away and to clean up the plant.
- G) It is recommended that the plant be filled as soon as possible with water or sewage from the following properties:

**Appendix D: Fault finding**

Symptom	Cause	Action
Strong Odour	Excess chemicals in the plant: Excessive laundry use Carry out a settlement test Drain, investigate venting	See appendix E See appendix E See appendix C Check that a high level vent is fitted to the house and is working correctly Carry out 12 month service and correct any faults found Check Compressors
Compressor stopped	Lack of rotation Switch off at the mains isolator	Switch on Check the supply board for a trip or fuse
	Power Failure	Inspect pipe and check all points for any leaks or splits
	Compressor is running but no turbulence	Check the compressor is operating and delivering air to the bio-zone
Polluted effluent	Check the compressor is operating and delivering air to the bio-zone Carry out a settlement test in appendix C	Check and repair any faulty parts Follow the fault finding guide in appendix E
Bio-zone chamber has grey colour	Check there is good supply of air to the plant/turbulent plant in Bio-zone!	Check compressors are operating correctly
Bio-zone has greyish to black colour and an offensive odour	Excessive laundry use	See do & don't section of this manual, laundry detergents



No. 1000

EU 2006/95/EC



No. 1000

WEEE Directive 2002/96/EC



**Manufacturer's information**

Client ref: ASP C2008-086B25.02

**Appendix E: Household practices: Do & Don'ts****Introduction**

When we take a bath, put the washing machine on or flush the toilet/lavatory, what happens to the waste water and sewage? It simply goes down the drain or waste pipe and is no longer our concern. But if your discharge leads to a protected treatment plant, particularly one using a biological treatment system, then it's worth paying some attention to what happens next!

If you don't, you could end up with a treatment plant which is not working efficiently and eventually run the risk of polluting your local environment and even facing possible prosecution as a result.

**What is sewage?**

Sewage is made up of not just the organic waste from toilets but also the chemicals and waste water from everyday activities such as washing, cleaning, cooking and washing clothes and dishes. The sewage from bathrooms, kitchens and laundries often follows in a series of drains that lead to a sewer. Most household or commercial premises treat sewage away from a series of sewers and is treated at a large-scale sewage treatment works. However, for houses and premises in remote or isolated locations where no mains drainage is available, other options such as cesspools or septic tanks and treatment plants have traditionally been used.

<b>Bio-zone has a very light brown colour and has few suspended solids. White sludge.</b>	<b>Lightly loaded</b>	If plant has just started or the effluent quality is OK, no further action. Otherwise contact Conder for advice.
<b>Bio-zone is black in appearance</b>	<b>Plant is organically over-loaded</b>	Check that no surface water is entering the plant.
	<b>Not enough air is getting to the bio-zone</b>	Check load to plant or if a de-sludge is required.
<b>Grease balls in the bio-zone.</b>	<b>Too much grease in effluent</b>	Check compressors and air intake.
<b>Final effluent contains many Solids.</b>	<b>Excessive laundry use</b>	Reduce grease in kitchen waste.
	<b>Carry out 12 month service</b>	See laundry section of do & don'ts.
		Only employ the plant or sludge if required.



Ref ID: 5400

26



Ref ID: 5400

25



## Manufacturer's information



Chemical ACP Chemicals & Chemicals



### Do's and Don'ts

#### DO:

#### Weekly Inspections

- Check that the autoclave is operating by listening for a gentle hum.
- Check the final effluent discharging from the unit at the sample point. If it is cloudy or contains suspended particles contact your maintenance provider.

Think before you put anything down the sink, toilet or drains

Tell your designated staff that you have a specialist sewage treatment plant and tell them how they can avoid having it.

Read the label and use the manufacturers' recommended doses for all household cleaning products

Use cleaning products safe and clean so the plant isn't overloaded

Spread your do's over throughout the week

Seek to find some washing, disinfectant powders and other cleaning products - the best ones plant will work most effectively with products that are user friendly

Use liquid cleaners for clothes washing and for dishwashers, use sparingly



### Don't:

Spring clean and use large amounts of cleaners and chemicals in one day

Have a 'washing day' - spread your washing throughout the week

Use household bleach and other strong chemicals indiscriminately

Keep cleaning on your hands of household cleaners and washing powders

Tip bottles of medicine, mouth wash etc. down the toilet

Put sanitary towels, tampons, disposable nappies, baby wipes, cotton wool, insect repellent pads etc down the toilet

Over flush the toilet unreasonably - use a water saving flush if it's fitted

Pour fat or grease from cooking down the sink or drains

Change oil in your chip pan and pour it down the drain

Use your waste disposal unit like a rubbish bin - use it sparingly

Pour garden chemicals or car engine oil down the drain

So how should I use cleaning products?



EPA 5050  
R-91-175-100

27



EPA 5050  
R-91-175-100



## Manufacturer's information



Clients ACP Clean Italia G.I.A. 00000000000000000000000000000000

### Laundry detergents

First you need to find out the level of hardness of your "hard water" (see section on water softeners). Once you know how hard or soft your water is, you can read the label on your laundry detergent and decide how much to use. The aim is to minimise the amount of detergent you use to limit its impact on the environment whilst ensuring you get the best results from your wash.

- It is recommended that you use washing liquids in an automatic dish-dropper rather than powders. You get the best results from having the liquid in the heart of the wash, a liquid is already in suspension and therefore "gets to work" quicker and it reduces the amount of product left in the washing machine dispenser or lost in the journey to the drain.

- For normal "coloured" washes try to use a washing product without added bleach. For white washes add a separate bleach such as the one produced by Ecover.

- Read the label and stick to the dosage recommended by the level of hardness of your water and to match the level of dirtiness of your washing. This is particularly important if you are using "concentrated" or "compact" liquids or powders because it is easy for your hand to spill and/or you to use far too much.

- Try to ensure you have a full load each time or use an energy-saving "half load" programme if you have one. Don't be tempted to overload as this will produce a good wash and could damage your machine in the longer term. A compactly packed machine should have enough space for you to put your hand in to place the liquid box on top of the washing.

- Normal wash is usually fine with the occasional very hot or "boil" wash, and not a problem to the treatment plant; however, this is not a good idea to do regularly, very hot washes as this could raise the plant temperature and affect the biological process.

- Your washing machine produces the largest quantity of waste when your treatment plant has to deal with. Don't have a "wash day" as this could produce too much water for the plant to handle in one go. Try to spread your washing throughout the week.

### Dishwasher products

Your dishwasher is probably the most "aggressive" cleaning product in your household. It needs to be to remove greasy plates, spoons and "soilily" dishes. As the Advertises' promise, it is therefore all the more important that you stick carefully to the manufacturers' recommended dosage. It is recommended that you use a liquid ratio (100g powder or tablet dosage) as this is understood to be more efficient.



Clients ACP Clean Italia G.I.A. 00000000000000000000000000000000

### Water softeners

Most dishwashers use softened water so there is less to ensure the salt deposit is stored & binged up because soft water increases the efficiency of the cleaning product and enables you to use only the minimum dosage of detergent.

Garment dry-cleaners, manufacturers, who pride themselves on their "low-water" energy-saving initiatives, recommend that you do not rinse your washing up under the hot tap before putting it in the dishwasher. Although this is a naturally common practice dishwashers and their cleaning products are now so effective that this is unnecessary - you are merely wasting energy and hot water.

### Other cleaning products

It is most important that you always follow the manufacturers' recommended dosage on all household cleaning products. Read the label - don't be tempted to use guesswork. Try to avoid using large amounts of cleaning products more often. If you follow the recommended dosage and use only small quantities on a regular basis they should not have any adverse effect on the treatment plant. However, a day's spring cleaning using massive amounts of household cleaners and disinfectants indiscriminately will affect the efficiency of the plant and destroy some of the bacteria. If the bacteria are harmed or killed they will eventually fester and come back but in the meantime your water would probably scream for help - depending on the amount of chlorine used.

### Water softeners

To reduce the quantity of laundry detergents you use you need to find out how hard your water is. You could phone your local water company (see 'Local Pages'). They would be able to tell you where your water comes on the hardness scale.

The hardness of water is determined by the amount of calcium and other minerals it contains. Hard water is rich in calcium which reduces the effectiveness of soap and detergents. There is a scale of water hardness in England: 0-5° very soft, 5-10° soft, 10-15° medium hard, over 15° hard. In line with EC recommendations all fabric washing products now carry advice on how much to use according to these levels of water hardness. Once you have identified whether your water is on the scale you can work out exactly how much detergent to use. In doubt you could phone the manufacturer for whom most offer a customer care phone service.

But to help you reduce the quantity of detergent still further - and save you money - you could try a separate water softener.



**Manufacturer's information**

FRANCE

Conder AD Orléans G.I.A.N.D. S.A.S.



FRANCE

Conder AD Orléans G.I.A.N.D. S.A.S.

**Commercial Water Softener**

Water softeners that involve a "soft" regeneration process can be very harmful to biological treatment systems. As the softener/organismal salt solution is used, there will be a risk to the micro-organisms in your biological sewage treatment plant. Domestic water softeners for a household should not present a problem. Please contact Conder Products if in doubt.

**Waste disposal units**


These do not inhibit the micro-organisms, but depending on use, they can present the treatment plant with considerable extra load. Much better to compost your vegetables/no peeling etc - it's greener and more environmentally friendly.

**Harmful substances**

The following list consists of known process inhibitors, though not limited to. Under no circumstances should they enter the treatment plant:

Grease Fluid, medicines, cooking oil or melted fat e.g. from a grill tray or chip pan, motor oils or other car products; garden chemicals such as weed killers or fertilisers; DIY products such as paints, white spirit, paint thinners and other solvents, glue, antifreezes, engine oil, dairy waste.

Just think before you throw any chemicals into the system - if in doubt, always dispose of elsewhere.

**Appendix F: Extension kit install**

31



SC 0100

00000000000000000000000000000000




**Manufacturer's information****Appendix G: Quick Installation Guide****Do:**

- Read the QSG Manual including appendices for full details.
- Keep the manual together with any drawings that were issued and any other communication (order acknowledgement, quotation, etc.)
- Take care when handling the unit - external and internal pipe work & electrical equipment could be damaged.
- Ensure adequate ventilation - the treatment panel is part of the foul drainage system and requires venting (see section 'Installation Instructions', p. 10).
- Use a suitable rated cable to connect the socket inside the Conder ASP unit to the electrical equipment (see 'Electrical Installation', p. 16).

**Don't:**

- Install a Conder ASP unit deeper than the supplied recess kit (i.e. do not extend the recess)
- Connect Conder units directly to the power supply (i.e. do not use a power source with a standard household earth leakage circuit breaker (PCO) in the power supply to the unit, unless specifically IEEE compliant). Then a dedicated device should be provided (see section 'Electrical Installation', p. 16).

Document Reference: GM1901  
Date: 20/07/2017  
Page: 23



34

Document Reference: GM1901

conder  
PRODUCTS